

Salt Marsh Restoration

through the
Beneficial Re-Use of Dredged Material

JACQUELINE JAHN
PROJECT ECOLOGIST, GREENVEST, LLC



Project Background

- **Objective:** Three trial projects to test the marsh restoration through beneficial re-use concept
- **Landowner:** NJ Division of Fish & Wildlife
- **Funding source:** Hurricane Sandy Coastal Resiliency grant (2-year)
- **Project Team:**
 - The Nature Conservancy
 - GreenVest
 - Princeton Hydro
 - The Wetlands Institute
 - NJDEP and more.



Project Background

Our Goals

- Trial the beneficial reuse of dredged material to restore salt marshes to prove the concept in NJ (can achieve ecological goals while inflicting no harm)
- Collaborate with other resource agencies to best use limited resources

Our Objectives

- Implement multiple trial projects on multiple different sites
- Monitor projects to document success and challenges
- Disseminate lessons learned to facilitate future projects



Monitoring

- Elevation
- Depth and duration of flooding
- Vegetation
- Wildlife communities
 - Fish
 - Birds
 - Macroinvertebrates
 - Benthic infauna
- Sediments
- Wave energy & flooding modelling
- Adaptive Monitoring (post-con)
- Lessons learned and Cost analysis



Trial Projects

- ☐ Ring Island Thin Layer Placement Demonstration Project
 - Aug – Sept 2014
- ☐ Ring Island Shorebird Nesting Habitat Creation
 - Aug – Sept 2014
- ☐ Avalon Thin Layer Placement Demonstration Project – Phase 1
 - Dec 2014 – Jan 2015
- ☐ Avalon Thin Layer Placement Demonstration Project – Phase 2
 - Nov 2015 – Feb 2016
- ☐ Fortescue Marsh, Dune and Beach Restoration
 - ongoing



Trial Projects

❑ Ring Island Thin Layer Placement Demo Project

- Aug – Sept 2014
- **Goal:** Raise elevation of marsh to enhance plant communities by adding a thin layer of dredged material
- 2 trial areas (1 acre total)
- 500-1,000 cy
- Spraying a sand/water slurry across the salt marsh from edge
- Placement ranged from 0.5 – 9"
- Patchy recovery of plant communities are beginning to recover
- **USACE & Barnegat Bay**
- **NJDEP & The Nature Conservancy**



Trial Projects

❑ Ring Island Shorebird Nesting Habitat Creation

- Aug – Sept 2014
- **Goal:** Elevate marsh above mean high tide to create shorebird nesting habitat by adding a thick layer of dredged sand
- 2 acre open sandy area
- ~6,000 cy
- Pumping sand/water slurry, dewatering and grading
- The site has become a haven for coastal wildlife:
 - American Oyster Catchers, Least Terns, and Black-backed Gulls
 - Horseshoe crabs and Terrapin turtles
- **USACE & Barnegat Bay**
- **NJDEP, TNC & The Wetlands Institute**



Trial Projects

❑ Avalon Thin Layer Placement Demonstration Project – Phase 1

- Dec 2014 – Jan 2015
- **Goal:** Fill unhealthy, expanding pools to restore/create contiguous marsh plain and raise the elevation of the surrounding marsh
- 2 trial areas (~5 ac total)
- ~5,000 cy
- Spraying a sand/water slurry across the salt marsh
- Limited containment
- Placement ranged from 0.5 – 18"
- **USACE & Barnegat Bay**
- **NJDEP & The Nature Conservancy**



Trial Projects

❑ Avalon Thin Layer Placement Demonstration Project – Phase 2

- Nov 2015 – Feb 2016
 - **Goal:** Fill unhealthy, expanding pools to create contiguous marsh plain and raise the elevation of the surrounding marsh
 - 5 placement areas (~35 ac total)
 - ~45,000 cy
 - Staging pipe in marsh and pumping a sand/water slurry into pools
 - Fully contained
 - Placement ranged from 0.5 – 24"
 - **USACE & Barnegat Bay**
 - **NJDEP, TNC, GreenVest & Princeton Hydro**





AVALON PROJECT SITE

The problem: Expanding pool/degraded marsh complexes threaten the integrity of the salt marsh island

The solution: Fill the pools to create contiguous marsh plain and raise the elevation of the surrounding marsh



AVALON PROJECT SITE

Project Implementation

1. Sediment testing


- 60:20:20 **SILT**:clay:sand
- Dioxin/furans
- Bulking
- **Channel Sediment: USACE & ERDC**
- **Marsh Sediment: NJDEP & Princeton Hydro**



AVALON PROJECT SITE

2. Project Design

- Target elevations
- Containment needs
- Construction constraints
- **GreenVest & Princeton Hydro**



AVALON PROJECT SITE

Project Implementation

3. Containment Installation


- Semi-permeable coconut fiber logs
- Small, shallow “confined disposal facilities”
- **GreenVest**



AVALON PROJECT SITE

4. Sediment placement

- Transport & dispersal
- 45,000cy over 40 acres
- **USACE & Barnegat Bay**
- **NJDFW & GreenVest**





AVALON PROJECT SITE

5. Planting

- Natural recruitment has already begun
- Planting will occur Spring 2017
- **GreenVest**





So how did we get it done?

Agency Collaboration!

- Early conversations between USACE – Philadelphia District and NJ Division of Fish & Wildlife right after Hurricane Sandy
 - Interest
 - Feasibility
 - Project sites
 - Funding
- Gathering a large multi-disciplinary project team and maintaining regular communication

09/11/2014

NJDEP's perspective at the outset

- ❖ Willingness and impetus came from viewing these as PILOT projects that will be carefully monitored
- ❖ NJDFW gathered trusted partners and set regular communication
- ❖ NJDFW invited reps from other NJDEP departments early on, who would participate in the project planning process



NJDEP's Project Team

NJDEP - Division of Fish & Wildlife

Office of Sediment & Dredging Technology

Office of Science

GREEN TRUST ALLIANCE

MANAGEMENT OF PROJECT IMPLEMENTATION

- GreenVest – project management, restoration design, construction oversight and implementation, monitoring
- Princeton Hydro – engineering, construction oversight, monitoring

THE NATURE CONSERVANCY

MANAGEMENT OF PROJECT MONITORING

- Stockton University – monitoring, modelling
- Rutgers University – monitoring
- The Wetlands Institute – monitoring, education



Project Planning Process

1. SITE ASSESSMENT

- DEP attended site visits
- Stated that the marsh must be degraded and BU must be the appropriate solution
- “This is a restoration project not a disposal project.”

2. CHANNEL SEDIMENT ASSESSMENT

- DEP performed independent assessment
- Contaminants: “like-on-like” policy; matching marsh areas and channel segments
- Texture: some consideration
- Bulking and consolidation: used to set max cy of dredged material



Project Planning Process

3. RESTORATION PROJECT DESIGN

- DEP reviewed several draft plans and participated in all design discussions
- Required the use of bio-benchmarks to set target elevations
- Required containment measures to protect tidal creeks and efficiently achieve target elevations
- Required detailed topographic survey to determine target volume of dredged material and to determine containment needs
- Target elevation was the only real success criteria but loose at that because of uncertainties in bulking and consolidation



Project Planning Process

4. PROJECT IMPLEMENTATION PLANNING

- DEP attended all planning discussions and meetings
- DEP attended pre-construction meetings with USACE and their dredging contractor, Barnegat Bay Dredging
- Required containment to be biodegradable
- Required a DEP representative out on the marsh during construction
- Required weekly communication on construction
- Set timing restrictions for sensitive wildlife
- Set guidelines on working during specific tidal conditions and night time
- Required grade stakes as a visual guide on when to stop pumping, but no fixed requirement to revisit an area to meet grade
- Set max. volume per marsh area, but allowed for easy permit modification due to uncertainties in bulking and consolidation
- Set guidelines on how to adaptively manage construction, especially any breaches in containment



Finally Permits!

- Permits required:
 - Coastal General Permit #24 for Habitat creation, restoration, enhancement
 - Clean Water Act Section 401 Water Quality Certificate
 - Coastal Zone Management Program Consistency Determination
- Project-specific conditions:
 - No dredging between April 1 and Aug 31
 - Max volume of dredged material
 - Permitted target elevations and volumes per area
 - Sediments w elevated levels of dioxins could only be placed within designated areas on the marsh (like-on-like)
 - Minimize/document dispersal of sediments beyond area boundaries
 - Minimize impact to marsh by equipment
 - Plant
 - Monitor
- The key to permitting this project was intense participation by DEP throughout



DEP during construction

Weekly communication and troubleshooting!
Allowances made for certain circumstances.



DEP after construction

A photograph of a coastal wetland area. In the foreground, there is a large, irregularly shaped, light-colored stone or concrete structure, possibly a breakwater or a large culvert, with patches of green grass growing in the crevices. Two people are visible in the middle ground: one person is kneeling on the grass, wearing a light blue shirt and a hat, and the other is standing, wearing a dark shirt and pants. In the background, there is a body of water and a distant shoreline with buildings and trees under an overcast sky.

Weekly communications on monitoring and adaptive management

- Interpreting results of monitoring
- Tracking unexpected results
 - Containment management
 - Vegetation die-off areas

NJDEP's thoughts going forward

- A bit cautious to move forward until these pilot projects are complete and lessons are derived.
 - Bulking and consolidation for better planning
 - Reaction of marsh to the dredged material (chemical and physical) to establish thresholds (marsh compaction, smothering depth)
 - Issues with containment
 - Success or failure of original, recruited and planted material at various depths (recovery trajectories)
 - Costs
- Working on developing a permit application checklist
- Working on site assessment policies and how to ID if a marsh is a candidate (established the Coastal Ecological Projects Committee)



Looking forward...

- Spring 2017 planting
- Continued monitoring within grant
- Acquiring funding to monitor long-term
- Publication of a team-authored white paper
- Distilling lessons learned for future projects

Thank you.

